






此知识产权属上海西芝矿机有限公司所有，未经许可不得向第三方提供。 The intellectual property rights of this document belongs to Shanghai Zenith Mineral Co.,Ltd. Providing to any third party without Zenith permission is not allowed.									
	C15X1315III反击式破碎机 C15X1315III impact crusher		地脚螺栓孔位置及单点载荷图 Anchor bolt hole position and single point load diagram	设计 Designed By		阶段 Stage	比例 Scale	版本 Edition	
				审核 Reviewed By		施工 construction	1:18	A	
	工艺审查 Technical Audit			吴海龙					
	上海西芝矿机有限公司 Shanghai Zenith Mineral Co.,Ltd.			标准审查 Standard Audit	周明月	第1页 Page1/1		共1页 Page1	
				批准 Approve	张培林				
		日期 Date	2025.12.01						



单电机重量: 1670Kg, 传动部件总重(电机、路轨、皮带轮): 2075Kg。
静载荷估算: 20.8KN; 动载荷估算: 41.5KN。
Single motor weight: 1670Kg, total weight of transmission components (motor, track, pulley): 2075Kg.
Static load estimation: 20.8KN; Estimation of dynamic load: 41.5KN.

此知识产权属上海西芝矿机有限公司所有, 未经许可不得向第三方提供。 The intellectual property rights of this document belongs to Shanghai Zenith Mineral Co.,Ltd. Providing to any third party without Zenith permission is not allowed.						
	设计 Designed By		阶段 Stage	比例 Scale	版本 Edition	H
	审核 Reviewed By		施工 construction	1:18	A	
	工艺审查 Technical Audit	吴海龙	第1页 Page1/1		共1页 Page1	
	标准审查 Standard Audit	周明月				
批准 Approve		张培林				
		日期 Date	2025.12.01			



此知识产权属上海西芝矿机有限公司所有，未经许可不得向第三方提供。

The intellectual property rights of this document belongs to Shanghai Zenith Mineral Co.,Ltd. Providing to any third party without Zenith permission is not allowed.







CI5X1315III反击式破碎机
CI5X1315III impact crusher

外形图
Outline Drawing

上海西芝矿机有限公司
Shanghai Zenith Mineral Co.,Ltd.


设 计 Designed By		阶 段 Stage	比 例 Scale	版 本 Ddition
审 核 Reviewed By		施 工 construction	1:35	A
工 艺 审 查 Technical Audit	吴海龙	第1页 Page1/1	共1页 Page1	
标 准 审 查 Standard Audit	周明月	BCI5X1315WX		
批 准 Approve	张培林			
日 期 Date	2025.12.01			




技术要求:
1、±0.000现场确定，平面位置根据工艺设计总图进行确定。
2、地面以下部分根据当地地质情况调整筏板厚度和尺寸大小，厂房或基础应根据基础图尺寸留有足够的高度和安装位置。
3、本图仅用于混凝土施工和设备安装参考，需在专业人员的指导下根据《用户手册》完成施工

Technical requirements:
1、±0.000 will be determined on-site, and the plane position will be determined according to the overall process design drawing.
2. The thickness and size of the raft below the ground should be adjusted according to the local geological conditions. The factory building or foundation should have sufficient height and installation position according to the dimensions of the foundation drawing.
3. This drawing is only for reference in concrete construction and equipment installation, and construction must be completed under the guidance of professional personnel according to the "User Manual"


此知识产权属上海西芝矿机有限公司所有，未经许可不得向第三方提供。 The intellectual property rights of this document belongs to Shanghai Zenith Mineral Co.,Ltd. Providing to any third party without Zenith permission is not allowed.											
	C15X1315III 反击式破碎机 C15X1315III impact crusher				子项工艺图 Sub item process diagram		设计 Designed By		阶段 Stage	比例 Scale	版本 Edition
							审核 Reviewed By		施工 construction	1:45	A
	上海西芝矿机有限公司 Shanghai Zenith Mineral Co.,Ltd.				标准审查 Standard Audit		工艺审查 Technical Audit	吴海龙	第1页 Page1/1 共1页 Page1		
							批准 Approve	周明月	BC15X1315ZX		
							日期 Date	张培林	2025.12.01		
12	12	11	1E	11							






基础平面布置图

Foundation layout plan




标高3.000m梁平法施工图

Construction Drawing of Beam Plane Method with an Elevation of 3.000m




矩形板洞口补强钢筋

注：洞口定位尺寸详平面。
Reinforcement steel bars for rectangular slab openings
Note-Detailed plan for the positioning size of the opening



柱平面布置图

Column layout plan



标高3.000m板平法施工图


WB1	WB2	WB3
WB1 h=200 B: X&Y#10@150 T: X&Y#10@150	WB2 h=500 B: X&Y#16@150 T: X&Y#16@150	WB3 h=700 B: X&Y#20@150 T: X&Y#20@150

注：未注明的楼板均为WB1；洞口定位配合工艺图确认；

Construction Drawing of Plate Leveling Method with an Elevation of 3.000m

Note: 1. Unspecified floor slabs are all WB1;

2. Confirmation of the process diagram for hole positioning coordination;



基础说明：

- 本工程平面位置详工艺设计总图。
- 本工程无地质报告，地基处理应根据地勘报告要求进行；基坑开挖应清除所有杂填土、回填土及其他不利土层，基坑底标高应根据现场实际情况与设计进行确定。
- 本工程地基基础设计等级为丙级，结构重要性安全系数为1.0。抗震等级：三级，抗震构造措施等级：三级；
- 图中尺寸除标高为m外其余均为mm。
- 材料：除垫层外混凝土强度等级均为C30（商品混凝土），钢筋HRB400（ Φ ），混凝土抗渗等级为P6；基础底部设置100mm厚C20素混凝土垫层，垫层每边超出基础外边缘100mm。
- 保护层厚度：基础、基础梁40mm，梁、柱35mm，板25mm。
- 本工程采用天然地基，采用梁板式筏形基础，基底压力为120kPa，要求地基承载力不得小于基础压力设计值，否则应采取相应措施以提高地基承载力。
- 筏板马蹬钢筋应与受力筋可靠连接，应保证上排钢筋的定位牢固，马凳筋的规格和间距由施工单位确定。
- 墙、柱竖向钢筋均伸入基础，插筋做法详国标《22G101-3》；
- 本工程基础施工完成后应及时进行回填，回填土施工应在上部结构施工前完成，基坑回填采用砂石垫层回填，回填前应清除基坑中的杂物，回填应在相对的两侧或四周同时均匀进行，并分层夯实每层虚铺厚度 $\leq 250\text{mm}$ ，压实系数 > 0.94 。
- 本图须按照国标图集《混凝土结构施工图平面整体表示法制图规则和构造详图（独立基础、条形基础、筏形基础及桩基承台）》（22G101-3）有关要求施工；图中未注明的构造做法均参照有关标准图集和规范。
- 板中配筋能拉通则拉通，遇到洞口则断开，并锚入洞口边梁、板内。楼板预留洞结合其他专业图纸预留，严禁后凿。
- 本图仅收用于工艺配合阶段，不作为施工依据；应根据审查机构审核的设计图纸进行施工。

Basic Description:

- The plane position of this project is detailed in the general process design drawing.
- There is no geological survey report for this project, and foundation treatment should be carried out according to the requirements of the geological survey report; The excavation of the foundation pit should remove all miscellaneous fill, backfill, and other unfavorable soil layers. The elevation of the foundation pit bottom should be determined based on the actual situation on site and the design.
- The foundation design level of this project is Class C, and the safety factor of structural importance is 1.0. Seismic grade: Level 3, seismic construction measure grade: Level 3;
- All dimensions in the figure are in mm, except for the elevation of m.
- Material: Except for the cushion layer, the concrete strength grade is C30 (commercial concrete), and the steel bar HRB400 (Φ), concrete impermeability grade P6; Set a 100mm thick C20 plain concrete cushion layer at the bottom of the foundation, with each side of the cushion layer extending 100mm beyond the outer edge of the foundation.
- Thickness of protective layer: 40mm for foundation and foundation beams, 35mm for beams and columns, and 25mm for slabs.
- The project adopts natural foundation, beam slab raft foundation, and the base pressure is 120kPa. It is required that the foundation bearing capacity should not be less than the design value of foundation pressure, otherwise corresponding measures should be taken to improve the foundation bearing capacity.
- The steel bars of the raft and horse pedals should be reliably connected to the load-bearing steel bars, and the positioning of the upper row of steel bars should be ensured to be firm. The specifications and spacing of the horse stool steel bars should be determined by the construction unit.
- The vertical reinforcement of walls and columns extends into the foundation, and the method of inserting reinforcement is detailed in the national standard "22G101-3";
- After the completion of the foundation construction of this project, backfilling should be carried out in a timely manner. The backfilling soil construction should be completed before the construction of the upper structure. The backfilling of the foundation pit should be carried out using a sand and gravel cushion layer. Before backfilling, debris in the foundation pit should be removed. The backfilling should be evenly carried out on both sides or around the opposite side, and each layer should be compacted in layers with a virtual paving thickness of $\leq 250\text{mm}$ and a compaction coefficient of ≥ 0.94 .
- This drawing must be constructed in accordance with the relevant structural requirements of the national standard atlas Rules for the Overall Plane Representation of Concrete Structure Construction Drawings and Detailed Structural Drawings (Independent Foundation, Strip Foundation, raft foundation and Pile Cap) (22G101-3); The construction methods not indicated in the figure refer to relevant standard atlases and specifications.
- If the reinforcement in the board can be pulled through, it will be pulled through, and when encountering an opening, it will be disconnected and anchored into the edge beam and board of the opening. The reserved holes in the floor slab shall be reserved in conjunction with other professional drawings, and it is strictly prohibited to chisel them afterwards.
- This drawing is only used for the process coordination stage and does not serve as a construction basis; Construction should be carried out according to the design drawings reviewed by the reviewing agency.

此知识产权属上海西芝矿机有限公司所有，未经许可不得向第三方提供。 The intellectual property rights of this document belongs to Shanghai Zenith Mineral Co.,Ltd. Providing to any third party without Zenith permission is not allowed.									
	C15X1315III反击式破碎机 C15X1315III impact crusher	结构施工图 Structural construction drawings	设计 Designed By		阶段 Stage	比例 Scale	版本 Edition		
	上海西芝矿机有限公司 Shanghai Zenith Mineral Co.,Ltd.		审核 Reviewed By		施工 construction	1:60		A	
			工艺审查 Technical Audit	吴海龙					
			标准审查 Standard Audit	周明月					
			批准 Approve	张培林					
			日期 Date	2025.12.01					
				第1页 Page1/1		共1页 Page1			
				BC15X1315GS					